

INTERIOR DECORATION AND CURATION WORK FOR MUNSHI PREMCHAND MEMORIAL MUSEUM AND LIBRARY, LAMHI, VARANASI

Sl. No.	Item Description	Quantity	Units
1	Research, Design, Display and Data Collection		
1.01	Providing of comprehensive research, design, and consultancy services, including team involvement and site work complete in all respect as per direction of engineer in charge M.R.	1.00	JOB
1.02	Providing of general and contextual reference display materials,- Content development, translation, theme development, visualization, writing and editing, data collection, script and storyboard preparation complete in all respecas per direction of E/I .M.R.	1.00	JOB
2	AV & IT Work Supply and Installation of QR code-enabled digital wall interface that triggers a lamp-lighting animation, serves interpretive multimedia content.		
2.01	Supply, Installation, Testing and Commissioning of 55 inch commercial LED Screen having 4k resolution of Lifetime running time of 50,000 hours and having Connectivity Interface: x2 HDMI (in), x2 DP (in & out), x1 DVI (in), x1 VGA (in), x2 RS232 (in & out). The screen shall be securely mounted using heavy duty brackets, ensuring proper alignment and stability, of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
2.02	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
2.03	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics and QR Code Scanner/Camera, audio setup, Touch Sensor Panel, other hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
2.04	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
3	Supply and Installation of an Interactive timeline with multimedia stories with visuals.		
3.01	Supply, Installation, Testing and Commissioning of 55 inch Capacitive Multi Touch Table with up to 40 simultaneous touch points having Resolution of 1,920 x 1,080; Pixel Pitch 0.54; Contrast Ratio 4000:1(without glass); of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete.M.R.	1.00	nos.
3.02	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, GeForce RTX 5080, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
3.03	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics, audio setup, Touch Sensor and controllers, other hardware, cabling, and software systems and IOT with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
3.04	Research, Design and Development of Content (Bi-lingual) including script and storyboarding as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
3.05	Design and Development of 3D animation, VFX, SFX, Voice over (Bi-lingual) as approved by the Consultant / Client handling all complete.M.R.	1.00	JOB
3.06	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
4	Supply and Installation of two wall Immersive Projection of Premchand's ancestral home.		
4.01	Supply, Installation, Testing and Commissioning of 32 inch Capacitive Multi Touch Table having Resolution of 1920 x 1080; Pixel Pitch (HxV) 0.315 x 0.315; Contrast Ratio 4000:1(without glass); of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.

4.02	Supply, Installation, Testing and Commissioning of High resolution commercial DLP laser phosphor projector of 8000 lumens; Resolution 1,920 x 1,200 (WUXGA); Color correction P7 RealColor; Embedded warp & blend engine; Active stereoscopic 3D; Lens type: FLD/FLD+; Motorized zoom, focus and lens shift of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	2.00	nos.
4.03	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, GeForce RTX 5080, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
4.04	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics and projection surface, audio setup, hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
4.05	Design, Supply, installation Testing, and Commissioning (DSITC) of All wiring and other Digital Projection accessory items required on site for Digital Projection from DB to the mentioned technology item all complete with integration, mapping etc.M.R.	1.00	JOB
4.06	Research, Design and Development of Content (Bi-lingual) including script and storyboarding as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
4.07	Design and Development of 3D animation, VFX, SFX, Voice over (Bi-lingual) as approved by the Consultant / Client handling all complete.M.R.	1.00	JOB
4.08	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
5	Supply and Installation of a large multi-touch LED wall with an intuitive UI where visitors can type or scan a QR code to upload their poems, quotes, or stories. - Share Your Thoughts		
5.01	Supply, Installation, Testing and Commissioning of Indoor P1.5 LED Display having P-1.5 INDOOR LED VIDEO WALL Module-40,Brand-Qiangli M Pro/Hikvision Refresh Rate-3840HZ; Module Size - 320 x 160 MM; Module Resolutions - 208 x 104 Dots; Brightness-550-700 Nits Power Supply-5 of approved make and model by the Consultant / Client with all required structure, hardware, cables, connectors, screws, transportation and handling all complete. M.R.	1.00	nos.
5.02	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
5.03	Supply, Installation, Testing and Commissioning of 32 inch Capacitive Multi Touch Table having Resolution of 1920 x 1080; Pixel Pitch (HxV) 0.315 x 0.315; Contrast Ratio 4000:1(without glass); of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
5.04	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics, audio setup, hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
5.05	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
6	Supply and Installation of a Interactive Quiz for literary quizzes about Premchand's works and life.		
6.01	Supply, Installation, Testing and Commissioning of Indoor P1.5 LED Display having P-1.5 INDOOR LED VIDEO WALL Module-40,Brand-Qiangli M Pro/Hikvision Refresh Rate-3840HZ; Module Size - 320 x 160 MM; Module Resolutions - 208 x 104 Dots; Brightness-550-700 Nits Power Supply-5 of approved make and model by the Consultant / Client with all required structure, hardware, cables, connectors, screws, transportation and handling all complete. M.R.	1.00	nos.
6.02	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.

6.03	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics, audio setup, Motion Detection Camera, IOT Pods (6-8), IOT Toolkit, other necessary hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
6.04	Research, Design and Development of Content (Bi-lingual) including script and storyboarding as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
6.05	Design and Development of 3D animation, VFX, SFX, Voice over (Bi-lingual) as approved by the Consultant / Client handling all complete.M.R.	1.00	JOB
6.06	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
7	Supply and Installation of a wall Projection of book with his stories, handwritten notes, and related visuals that bring his words to life. - Flip Book with Projection		
7.01	Supply, Installation, Testing and Commissioning of High resolution commercial projector of 7,000 ANSI Lumens Brightness with 8.3 mega pixels utilizing 4K UHD (3840 x 2160) resolution and Throw Ratio of 1.53 to 2.45 with interchangeable lens of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
7.02	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
7.03	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics, Gesture Sensor, other necessary hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
7.04	Research, Design and Development of Content (Bi-lingual) including script and storyboarding as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
7.05	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
8	Supply and Installation of the Digital Bioscope for movie adaptations, or theatrical scenes related to Premchand's works, using simple touch controls or buttons.		
8.01	Supply, Installation, Testing and Commissioning of 43 inch commercial LED Screen having 4k resolution of Lifetime running time of 50,000 hours and having Connectivity Interface: x2 HDMI (in), x2 DP (in & out), x1 DVI (in), x1 VGA (in), x2 RS232 (in & out). The screen shall be securely mounted using heavy duty brackets, ensuring proper alignment and stability, of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	3.00	nos.
8.02	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, GeForce RTX 5070, 2 TB SSD, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
8.03	Design, Supply, installation Testing, and Commissioning (DSITC) of custom built structural encasing with graphics and cooling system, Button Control Panel, headphones, audio amplifier, other necessary hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
8.04	Research, Design and Development of Content (Bi-lingual) including script and storyboarding as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
8.05	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
9	Supply and Installation of Interactive Wall with touch based solution - Personality of Munshi Premchand		
9.01	Supply, Installation, Testing and Commissioning of 32 inch Capacitive Multi Touch Table having Resolution of 1920 x 1080; Pixel Pitch (HxV) 0.315 x 0.315; Contrast Ratio 4000:1(without glass); of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.

9.02	Supply, Installation, Testing and Commissioning of High resolution commercial DLP laser phosphor projector of 8000 lumens; Resolution 1,920 x 1,200 (WUXGA); Color correction P7 RealColor; Embedded warp & blend engine; Active stereoscopic 3D; Lens type: FLD/FLD+; Motorized zoom, focus and lens shift of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
9.03	Supply, Installation, Testing and Commissioning mini pc with Intel® Core™ Ultra 7 265 (13 TOPS NPU, 20 cores, up to 5.3GHz), Windows 11 Pro, 32 GB: 2 x 16 GB, DDR5, up to 5600 MT/s, non-ECC, 2 TB SSD, GeForce RTX 5080, TLC of approved make and model by the Consultant / Client with all required hardware, cables, connectors, transportation and handling all complete. M.R.	1.00	nos.
9.04	Design, Supply, installation Testing, and Commissioning (DSITC) of All structural encasing with graphics and projection surface, audio setup, hardware, cabling, and software systems with full integration, testing, and commissioning. Scope includes alignment and calibration of equipment, and final handover after performance verification. M.R.	1.00	JOB
9.05	Design, Supply, installation Testing, and Commissioning (DSITC) of All wiring and other Digital Projection accessory items required on site for Digital Projection from DB to the mentioned technology item all complete with integration, mapping etc.M.R.	1.00	JOB
9.06	Research, Design and Development of Content (Bi-lingual) including script and storyboarding as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
9.07	Design and Development of 3D animation, VFX, SFX, Voice over (Bi-lingual) as approved by the Consultant / Client handling all complete.M.R.	1.00	JOB
9.08	Design and Development of UI/UX as approved by the Consultant / Client handling all complete. M.R.	1.00	JOB
10	Fabrication and Installation of door cladding using 19/12 mm waterproof ply of Century make finished with 1mm thick Laminate complete after giving anti-termite treatment with tools, tackles, labour charges, transportation and handling all complete as per brief/design/concept/model/ prototype/ drawings and as per directions of Site-in-Charge M.R	1.79	Sqm
11	CEMENT PLASTER ((IN COARSE SAND)) 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)DSR 2023, Vol - II , Item No - 13.4.1	953.64	Sqm
12	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. DSR 2023, Vol -I , Item no - 11.41A.1.5	287.00	Sqm
13	Providing and fixing on wall face unplasticized Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameterDSR -2023,Vol-I Page No- 205, Item No - 12.41.1	16.00	Rmt
14	Providing and fixing on wall face unplasticized - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 75 mm DSR - 2023,Vol-I Page No- 205, Item No - 12.42.1.1	4.00	each
15	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticized Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 75 mm bend DSR -2023,Vol-I , Item No - 12.42.5.1	4.00	each
16	Providing and fixing on wall face unplasticized - PVC moulded fittings/ accessories for unplasticized Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Shoe (Plain) 75 mm Shoe DSR -2023,Vol-I , Item No - 12.42.6.1	8.00	each
17	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete. 75 mm DSR - 2023,Vol-I , Item No - 12.43.1	12.00	each

18	Providing fitting and fixing of Podiums and showcases made of 19/12 mm Plywood Century IS710 with 32 mm x 32 mm x 3.2 mm MS section frame work finished with 1 mm laminate as per design with all fixtures and fittings, tools, tackles, transportation and handling all complete M.R.	14.43	Sqm
19	Providing fitting and fixing of Wall Panels and Partitions made of 19/12 mm waterproof plyboard of Century make duly fitted on iron frame 32x32x3.2 mm raised 2" finished with 1 mm laminate as per design with all fixtures and fittings, tools, tackles, transportation and handling all complete M.R.	195.67	Sqm
20	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess 25/32mm including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. DSR (E& M) 2025 item no - 1.20.2/3	250.00	Rmt
21	Supplying and drawing 3 x 1.5 sq. mm; 3 x 2.5 sq.mm; 3 x 4 sq.mm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface PVC conduct with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. DSR (E& M) 2025 item no - 1.17.3/4/21	853.00	Rmt
22	Supplying and fixing of 2 Module; 8Module; 12Module, GI box along with modular base & cover plate for modular switches in recess etc. with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. DSR (E& M) 2025 item no - 1.27.1/5/6	27.00	nos.
23	Supplying and fixing following 5/6 amps; 3 pin 5/6 A socket outlet modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. DSR (E& M) 2025 item no - 1.24.1/4	75.00	nos.
24	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. DSR (E& M) 2025 item no - 1.32	15.00	nos.
25	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc.with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. (But without MCB/RCCB/Isolator). 16 way, Double door DSR (E& M) 2025 item no - 2.3.4	3.00	nos.
26	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. . (Note : Vertical type MCB TPDB is normally used where 3 phase outlets are required.) 12 way(4+36), Double door DSR (E& M) 2025 page no 11 item no - 2.5.3	2.00	nos
27	Providing and fixing following rating and breaking capacity and pole MCCB in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. 125 Amp, 36 KA, FPMCCB DSR (E& M) 2025 item no - 2.2.14	4.00	nos
28	Supplying and fixing Single / Double Pole 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning with all fittings, fixtures and all related materials, tools, tackles, transportation & handling all complete. DSR (E& M) 2025 item no - 2.10.1/3	26.00	nos
29	Supply, Installation, Testing and Commissioning of 12 W LED 360 degree moveable surface cylindrical spot light c/w adapter with appropriate colour temperature and minimum CRI >100+, PF>0.95, CCT – 3000k and design as approved by the competent authority with all fixtures and fittings, tools, tackles, transportation and handling all complete. Rate to include all necessary hardware. M.R.	35.00	nos
30	Supply Installation, Testing and Commissioning of 12 W Ultra slim LED downlighter c/w adapter to be installed ceilings with appropriate colour temperature and minimum CRI>80, PF>0.95, CCT – 3000k and design as approved by the competent authority with all fixtures and fittings, tools, tackles, transportation and handling all complete. Rate to include all necessary hardware. M.R.	93.00	nos

31	Supply, Installation, Testing and Commissioning of LED Track Light ,Wattage-10 W, CRI>90, PF>0.95, CCT - 3000/4000/6500 K and design as approved by the Consultant / Client with all fixtures and fittings, tools, tackles, transportation and handling all complete. Rate to include all necessary hardware. M.R.	116.00	nos
32	Supply Installation, Testing and Commissioning of Ceiling Mounted Tracks - Two wire track Material- Copper wire Fitting-PDC AL and design as approved by the Consultant / Client with all fixtures and fittings, tools, tackles, transportation and handling all complete. Rate to include all necessary hardware. M.R.	47.00	nos
33	Supply, Installation, Assembling, Testing and Commissioning of LED Al Profile Channel Wattage - 10W/m encapsulated clear PU flex, should be at least IP 67 3000K 24Vdc CRI >80 MacAdam step 3 Beam angle: 120°, Should be equipped with dot less homogenous lighting effect Electronic driver ON/OFF (External driver); Copper coated strip, Silicone moulded diffuser, End cap,Clip, Lumen Maintenance (LM80) and Technical Memorandum (TM21), Lifespan of the luminaire > 50,000 hours at 40°C. Operating ambient temperature range is from - 15°C to +50°C. Driver efficiency >70%, Power factor >0.80, Surge protection 3KV.IES, LM 79, LM 80, as approved by the Consultant / Client with all fixtures and fittings, tools, tackles, transportation and handling all complete. Rate to include all necessary hardware. M.R.	21.00	Rmt
34	Lum sum Charges for Setting up a Control panel along with procurement and laying wiring for synchronization of all Exhibit lighting on a server and control panel fabrication. Setting up a control panel along with MCB ELCB PLC etc. and safety panels. Make: Customized M.R.	1.00	nos
35	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.DSR 2023, Vol -II Item no -13.80	1156.00	Sqm
36	Providing and application of 3 coats of paint of Asian Paints brand (Archi Paint) on wall surfaces as per specified shade after preparation of surfaces with waterproofing treatment and putty as required over wall primer with due ground preparation with trowel / roller finish in uniform application as per design with all fixtures and fittings, tools, tackles, transportation and handling all complete M.R.	1285.00	Sqm
37	Providing fitting and fixing of Arched Panel with pillars fabricated with (Mixed media) and artistic painted background with weather proof coating; Fibre glass chopped strand (matt) -450gm/m2; General purpose (G.P) polyester resin; Fiberglass woven roving – density 610 gsm; Hardener Catalyst 2% concentrated and best quality pigments of specific colour to be used with and Display Narrative and Photo Panels made of 19/12 mm waterproof plyboard of Century make duly fitted on iron frame 32x32x3.2 mm raised 2" finished with 1 mm laminate with GFRC arches and niches as per design with all fixtures and fittings, tools, tackles, transportation and handling all complete M.R.	8.00	nos
38	Providing fitting and fixing of UV Digital printing on 3M 180c front lit substate with 1200 dpi output with UV protected cold matt/gloss lamination of 125 microns mounted on 1mm thick back support and photo - narrative panels printed on UV Digital printing W210 translite film of 225 microns with 1200 dpi output with UV protected cold matt/gloss lamination of 125 microns mounted on 3mm thick acrylic sheet of 32800 kgf/cm² tensile strength fitted on .75 inch black anodised aluminium clipon frame as per design with all fixtures and fittings, tools, tackles, transportation and handling all complete M.R.	26.12	Sqm
39	Providing fitting and fixing of UV Digital printing on 3M 180c front lit substate with 1200 dpi output with UV protected cold matt/gloss lamination of 125 microns mounted on substrate as per design with all fixtures and fittings, tools, tackles, transportation and handling all completeM.R.	84.26	Sqm
40	supply of Executive Table, Particle Board Top SIZE W1950 X D1750 X H750 MODEL NO NUMERO 6 MAKE GICKEN	1.00	nos.
41	supply of High Back Chair, Wooden Frame, Wooden Arm, Torsion Bar, Gas lift, Wooden Base MODEL NO GP 105 MAKE GICKEN	1.00	nos.
42	supply of Visitor Chair, Wooden Frame, Cushion Arm, Chrome Plated pipe stand STEPHEN 3 CIVIC 3 MAKE GICKEN	6.00	nos.
43	supply of Three Seater Sofa, Wooden Frame, Wooden Gold Plated Leg, Size (in mm): 2120(L) X 900(D) X 850(H) MODEL NO STEPHEN 3 MAKE GICKEN	1.00	nos.
44	supply of Single Seater Sofa, Wooden Frame, Wooden Gold Plated Leg, Seat Back Asmara Fine Leatherette Tapestry Size (in mm): 920(L) X 900(D) X 850(H) MODEL NO STEPHEN 1 MAKE GICKEN	2.00	nos.

45	supply of Centre Table, Toughened Clear Glass 12mm Thick, Lower Shelf 18mm PLPB, Wooden Frame MODEL NO PLAZA 1 MAKE GICKEN	1.00	nos.
46	supply of Steel Almirah, 2 Glass Doors, 2 Steel Doors & 2 Drawers, Adjustable Shelf, Thickness 0.8mm MODEL NO GMS13 MAKE GICKEN	1.00	nos.
Total in Figures			